

ARC MAINTENANCE WORK SUMMARY OF APPLE PLANT AARTI CHEMICAL,VAPI

RELIABLE ENGINEERING SUMMARY SHEET JULY-2025

Item NO	Service No	Item Description	Unit	Per Unit Rate	P.NO 1	P.NO 2	P.NO 3	P.NO 4	P.NO 5	TOTAL QTY	AMOUNT
70	ESFLEX20000006	CABLE LAYING FLEX. 3-4C X 1 0/1.5 SQMM	M	6.00	16	15		5		36	216
160	ESFLEX20000013	CABLE LAYING FLEX EART. 1C X 1.5-6.0 SQMM	M	7.00		10	10			20	140
260	ESFLEX20000023	CABLE REMOVE FLEX. 3-4C X 1.0/1.5 SQMM	M	3.00	10				10	20	60
620	ESARMO20000054	CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM	M	20.02	8		48	25		81	1621.62
860	ESARMO200000862	OLD CABLE DRESSING ONLY-RUN. MT. TRAY	M	45.00				6		6	270
1100	ESARMO20000096	CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM	M	10.78	48	15	35			98	1056.44
1490	ESCOND20000134	CONDUIT LAYING FOR CABLE (U/O GND)-1.5"	M	13.07	18					18	235.26
1560	ESCOND20000141	CONDUIT REMOVE FOR CABLE (U/O GND)-1.5"	M	6.53	10					10	65.3
2200	ESINST20000199	CAB GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM	NOS	54.95	1		7	5		13	714.35
2840	ESREMO20000246	REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM	NOS	23.00	4	3	4	1		12	276
4920	ESFAB 20002565	INSTL CAB TRAY GI/FRP(PER/LAD)25-75MM	M	51.98		70	3			73	3794.54
5230	ESFAB 20010123	FAB&INST GI/FRP TRAY L/Z/T SUP.225-300MM	NOS	196.00			1			1	196
5240	ESFAB 20010124	FAB&INST GI/FRP TRAY L/Z/T SUP.350-450MM	NOS	225.00			1			1	225
5410	ESREMO20002595	REM CAB TRAY GI/FRP(PER/LAD)225-400MM	M	45.00	3.6			1		4.6	207
6310	ESINST20000494	INSTALLATION OF PB STATION-FLP	NOS	190.00			1			1	190
6580	ESREMO20000527	REMOVAL OF PB STATION-FLP	NOS	78.65			2			2	157.3
6750	ESELEC20000545	ELECTRICIAN	D	750.00	1	1		2	1	5	3750
6770	ESELEC20002621	MAN POWER SUPPLY - HELPER	D	600.00				2	2	4	2400
6790	ESELEC20000892	SHIFT. INST. CART. BOX 2'X3' STORE TO WS	NOS	181.50	4	7				11	1996.5
6960	ESELEC20000916	LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT	NOS	600.00				5	5	10	6000
6990	ESELEC20000922	SHIFT. / LOAD/UNLOAD OF MOTOR UPTO 15 HP	NOS	203.00		1				1	203
TOTAL AMOUNT										23774.31	



5. Anti Apple organic

DATE: 04/06/02/2025

Sub. Electrical

Page No. 02

[illegible]

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory

Aarti Apple organic

DATE: 3/10/02/2025

Sub. Electrical

Page No. 03

No.	Line Item No.	Description (Work Details)	UNIT	QUANTITY
1.		300X300X200 mm Earthing strip (H) Support fitting	Nos	01
2.		19mm gland remove	Nos	01
3.		4CX2.5 Sqmm cable laying	mtr	18
4.		19mm gland fitting	Nos	04
5.		6A FLP Push bottom Remove	Nos	02
6.		FLP Push bottom Install	Nos	01
7.		3CX1.5 Sqmm cable remove 1st floor R-212	mtr	30
8.		3CX1.5 Sqmm cable laying 1st floor ATR-218	mtr	25
9.		19mm gland Remove.	Nos	01
10.		19mm gland Install	Nos	01
11-02-2025				
1.		150X400 mm MSCT Support fitting	Nos	01
2.		19mm gland Remove.	Nos	02
3.		2CX2.5 Sqmm Earthing wire laying	mtr	10
4.		19mm gland fitting	Nos	02
5.		4CX2.5 Sqmm cable remove	mtr	05
6.		4CX2.5 Sqmm cable laying	mtr	05
7.		50mm C/I tray fitting	mtr	03

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory



Aarti Apple Organic

DATE: 13/11/2025

Sub. Electrical

Page No. 04

No.	Line Item No.	Description (Work Details)	UNIT	QUANTITY
1.		19mm gland fitting	Nos	05
2.		19mm gland remove.	Nos	01
3.		4CX2.5 Sqm cable dressing	mtr	06
4.		50mm GT tray remove.	mtr	01
5.		2CX2.5 Sqm Heat tracing cable laying	mtr	05
6.		4CX2.5 Sqm cable laying	mtr	25
7.		Diesel drum shifting Panel room to gate(1) loading on tempo gate-01	Nos	01
8.		200 ltr Diesel Drum unloading on tempo and shifting gate-1 to Panel room	Nos	01
9.		200 ltr Diesel drum shifting Panel room to High noise area	Nos	01
10.		100 ltr Diesel fill up to Diesel tank		
11.		Diesel Drum shifting High noise Area to Panel room	Nos	01
12.		5HP motor loading on tempo & DPL and unloading on tempo gate-1 and shifting Boiler area.	Nos	01
14/15-02/2025				
1.		man power Supply Electrician	Nos	02
2.		man Power Supply Helper	Nos	02

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory



DATE: 20/02/2025

Page No. 05

Prepared By

Checked By

For, Reliable Engineering


Authorised Signatory



ARC MAINTENANCE WORK SUMMARY OF APPLE PLANT AARTI CHEMICAL,VAPI

RELIABLE ENGINEERING SUMMARY SHEET MAY-2025

Service No	Item Description	Unit	Per Unit Rate	P.NO 1	P.NO 2	P.NO 3	P.NO 4	P.NO 5	TOTAL QTY	AMOUNT
ESFLEX20000006	CABLE LAYING FLEX. 3-4C X 1.0/1.5 SQMM	M	6.00				20		20.00	120.00
ESFLEX20000013	CABLE LAYING FLEX.EART.1C X 1.5-6.0 SQMM	M	7.00	11					11.00	77.00
ESFLEX20000030	CABLE REMOVE FLEX.EART.1C X 1.5-6.0 SQMM	M	3.38		4				4.00	13.52
ESARMO20000054	CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM	M	20.02	27					27.00	540.54
ESARMO200000862	OLD CABLE DRESSING ONLY-RUN. MT. TRAY	M	45.00		4		25		29.00	1305.00
ESARMO20000096	CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM	M	10.78	22					22.00	237.16
ESCOND20000134	CONDUIT LAYING FOR CABLE (U/O GND)-1.5"	M	13.07				10		10.00	130.70
ESINST20000199	CAB. GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM	NOS	54.95	4			1		5.00	274.75
ESREMO20000246	REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM	NOS	23.00	3					3.00	69.00
ESLIGH20000328	INSTAL. T/L FIT.1X40W / 2X40W FLP INDUST	NOS	302.50		1	2			3.00	907.50
ESREMO20000403	REMOVE T/L FIT.1X40W / 2X40W FLP INDUST	NOS	151.25		1	2			3.00	453.75
ESFAB.20002565	INSTL CAB TRAY GI/FRP(PER/LAD)25-75MM	M	51.98		2				2.00	103.96
ESREMO20002611	REMOVAL MS TRAY L/Z/T SUP.400-600MM	NOS	102.99		1				1.00	102.99
ESELEC20000545	ELECTRICIAN	D	750.00		2		2	6	10.00	7500.00
ESELEC20002621	MAN POWER SUPPLY - HELPER	D	600.00	2	1				3.00	1800.00
ESELEC20000891	SHIFTING OF INST. FROM PLANT TO STORE/WS	NOS	66.55			12			12.00	798.60
ESELEC20000892	SHIFT. INST. CART. BOX 2'X3' STORE TO WS	NOS	181.50			7	3		10.00	1815.00
ESELEC20000893	SHIFT. CV-FT STORE / WS TO PLANT UPTO 2"	NOS	201.28			1			1.00	201.28
ESELEC20000916	LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT	NOS	600.00	1		3	1		5.00	3000.00
ESELEC20000922	SHIFT. / LOAD/UNLOAD OF MOTOR UPTO 15 HP	NOS	203.00			1			1.00	203.00
TOTAL AMOUNT										19653.75



DATE: 01/5/03/2025

Page No. 01

[illegible]

Checked By


Authorised Signatory



Acridi Apple organic

DATE: 7/08/03/2025

Electronics

Page No. 02

[illegible]

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory



Aarti Apple Organic

DATE: 11/12/03 / 2025

b. Electrical

Page No. 03

Line Item No.	Description (Work Details)	UNIT	QUANTITY
1.	45W Well glass light remove	Nos	01
2.	45W well glass light fitting	Nos	01
3.	200ltr Diesel Drum shifting Panel room to High noise Area	Nos	01
4.	Diesel Drum shifting High noise area to Panel room	Nos	01
5.	24V Light transformer shifting gate-1 and loading on tempo & unloading to DRL	Nos	01
6.	45W light shifting gate-1 to loading on tempo & unloading to DRL	Nos	01
7.	Push bottom shifting gate-1 and loading on tempo & unloading to DRL	Nos	02
8.	0.5 HP motor shifting gate-1 and loading on tempo & unloading to DRL	Nos	01
9.	Wall fan shifting gate-1 and loading on tempo & unloading to DRL	Nos	01
10.	VV lamp box shifting VCB room to F & T office	Nos	05
13-03-2025			
1.	45W Well glass light Remove.	Nos	01
2.	45W well glass light fitting	Nos	01
3.	Diesel Drum unloading on tempo gate-1 and shifting to Panel room	Nos	01

Prepared By

Checked By

[Signature]

For, Reliable Engineering

Authorised Signatory



DATE: 15/7/03/2025

Page No. 04

For, Reliable Engineering

Checked By

Authorised Signatory



Art! Apple organic

DATE: 22/25/03/2025

b. Electrical

Page No. 05

[illegible]

Prepared By

Checked By

For, Reliable Engineering,

Authorised Signatory



ARC MAINTENANCE WORK SUMMERY OF APPLE PLANT AARTI CHEMICAL,VAPI										
RELIABLE ENGINEERING SUMMERY SHEET MAY-2025										
Service No	Item Description	Unit	Per Unit Rate	P.NO 1	P.NO 2	P.NO 3	P.NO 4	P.NO 5	TOTAL QTY	AMOUNT
60	ESFLEX20000013 CABLE LAYING FLEX EART 1C X 1 5-6 0 SQMM	M	7.00	16	12	8			36	252.00
260	ESFLEX20000023 CABLE REMOVE FLEX. 3-4C X 1.0/1.5 SQMM	M	3.00		12				12	36.00
490	ESARMO20000042 CABLE LAYING ARM. 1T X 1/1.5 SQMM	M	20.02				5		5	100.10
620	ESARMO20000054 CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM	M	20.02	18	5		5		28	560.56
860	ESARMO200000862 OLD CABLE DRESSING ONLY- RUN. MT. TRAY	M	45.00		6	5			11	495.00
970	ESARMO20000084 CABLE REMOVE ARM. 1T X 1/1.5 SQMM	M	10.78				15		15	161.70
1100	ESARMO20000096 CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM	M	10.78			10	5		15	161.70
2200	ESINST20000019 CAB. GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM	NOS	54.95	5	2		4		11	604.45
2840	ESREMO200000246 REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM	NOS	23.00				8		8	184.00
3630	ESLIGH200000315 INSTAL. OF EARTH. STRIP 35-50 MMX 5-6 MM	M	56.00			6			6	336.00
3890	ESLIGH200000337 INSTAL. & CONN. OF CEILING/WALL MOUNT FAN	NOS	165.77			1			1	165.77
4660	ESREMO200000403 REMOVE T/L FIT. 1X40W / 2X40W FLP INDUST	NOS	151.25			1			1	151.25
4920	ESFAB.20002565 INSTL. CAB TRAY GI/FRP(PER/LAD)25-75MM	M	51.98		1				1	51.98
5010	ESFAB.20002571 DRIL. & INST ANCHOR FAST.4-10 X 100/150MM	NOS	41.20	16					16	659.20
5020	ESFAB.20002572 DRIL. & INST ANCHOR FAST.12-30 X100/150MM	NOS	47.08	16	4	1			21	988.68
5300	ESFAB.20002591 FAB. & INST. MS TRAY C-CLAMP 300-600MM	NOS	242.00	2					2	484.00
5410	ESREMO200002595 REM. CAB TRAY GI/FRP(PER/LAD)225-400MM	M	45.00			3			3	135.00
5600	ESREMO200002606 REMOVAL GI TRAY L/Z/T SUP.100-200MM	NOS	88.28			1			1	88.28
6750	ESELEC200000545 ELECTRICIAN	D	750.00	1	3				4	3000.00
6760	ESELEC200000546 FITTER / WELDER	D	700.00					2	2	1400.00
6770	ESELEC20002621 MAN POWER SUPPLY - HELPER	D	600.00	1		3	1		5	3000.00
6780	ESELEC200000891 SHIFTING OF INST. FROM PLANT TO STORE/WS	NOS	66.55		1				1	66.55
6840	ESELEC20002623 SHIFT. BIG CABLE DRUM STORE - W.S.	NOS	442.75				1		1	442.75
6960	ESELEC200000916 LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT	NOS	600.00	2		3	4		9	5400.00
TOTAL AMOUNT										18924.97



Aarti Apple organic

DATE: 1/31/04/2025

Page No. 01

Electrical

[illegible]

Prepared By

Checked By

For, Reliable Engineering .

Authorised Signatory

Aarti Apple organic

DATE: 04/08/04/2025

b. Electrical

Page No. 02

[illegible]

Prepared By

Checked By

For, Reliable Engineering.

Authorised Signatory

Aarti Apple organic

DATE: 10/11 / 04 / 2025

b. Electrical

Page No. 03[illegible]

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory

Aarti Apple organic

DATE: 15/10/04/ 2025

Sub. Electrical

Page No. 64

[illegible]

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory

DATE: 22/04/2025

Electrical

Page No. 05

Prepared By

Checked By

For, Reliable Engineering

Authorised Signatory

Service Work Order (SWO)	3190012304	Business Partner Name: RELIABLE ENGINEERING Business Partner Code: (310020514) Address : Contact No.:7283834777 Email : chirag.reliable@gmail.com GSTIN : 24AATFR5694L1Z9
SWO Release Date	24.06.2025	
Current Revision Number	0	
Current Rev Release Date	24.06.2025	
Purchase Group	Pilot Mat & Ser	
Payment Term	IV2	
Sourcing Project Number		
Quotation Reference		
ARC/OLA Reference	7500005787	
LD Term		
Incoterm	FOR AIL Site	

Dear Sir,

We have pleasure to entrust you with our order for the services mentioned below and shall appreciate your executing the same as per the instructions given herein.

Parent Line	Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
10		Electrical Cable works may-2025 Mobilization date : Delivery date : 24.06.2025 Agreement no.7500005787-10				
	10	Service Code : INLYDCBF1A0013 Service Description : CABLE LAYING FLEX.EART.1C X 1.5-6.0 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - FLEXIBLE CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - INCLUDES LAYING & DRESSING OF FLEXIBLE CABLE - TIE UP AT EACH 300 MM BY USING CABLE / TIE. - THIS DOESN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	36.000	M	7.00	252.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
20	Service Code : INRMDCBFIA0007 Service Description : CABLE REMOVE FLEX. 3-4C X 1.0/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP -FLEXIBLE CABLE UNDRESSED & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - REMOVAL OF FLEXIBLE CABLE - DRESSING OF CABLES IS INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING.	12.000	M	3.00	36.00
30	Service Code : INLYDCBA1A0011 Service Description : CABLE LAYING ARM. 1T X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES LAYING & DRESSING OF ARMOURED CABLE - TIE UP AT EVERY 300 MM BY USING WIRE / TIE. - THIS DOESN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	5.000	M	20.02	100.10

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
40	Service Code : INLYDCBA1A0024 Service Description : CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMoured CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES LAYING & DRESSING OF ARMoured CABLE - TIE UP AT EVERY 300 MM BY USING WIRE / TIE. - THIS DOESN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	28.000	M	20.02	560.56

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
50	Service Code : INLYDCBA1A0042 Service Description : OLD CABLE DRESSING ONLY-RUN. MT. TRAY PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK: - OLD CABLE DRESSING IS APPLICABLE FOR DRESSING OF OLD CABLES DUE TO HOUSEKEEPING OR UNSAFE CONDITION JOBS. - OLD CABLE DRESSING MEANS: DRESSING OF EXISTING MULTIPLE CABLES UPTO 10 NOS. IN A TRAY MEASUREMENT WITH RUNNING METER LENGTH OF TH - IF CABLES ARE MORE THAN 10 NOS. THEN WILL BE IN MULTIPLICATION OF 10 EQUALS TO 1, IF CABLES ARE 15 THE RATE WILL BE DOUBLE, IF CAB - IF CABLE OD IS 1-30 MM (ALL INSTRUMENTATION CABLES - UPTO 48 CORE & 24 PAIR & POWER CABLES UP TO 1 TO 4 CORE 16 SQMM) THEN RATE IS - IF CABLE OD IS 31 MM AND ABOVE (ALL INSTRUMENTATION CABLES - ABOVE 48 CORE or 24 PAIR & POWER CABLES 1- 4 CORE ABOVE 16 SQMM THEN - MATERIAL FOR REDRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	11.000	M	45.00	495.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
60	Service Code : INRMDCBA1A0011 Service Description : CABLE REMOVE ARM. 1T X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE UNDRESSING & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES ARMOURED CABLE UNDRESSED & REMOVAL. - DRESSING OF CABLE IS INCLUDED. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING	15.000	M	10.78	161.70

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
70	Service Code : INRMDCBA1A0024 Service Description : CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE UNDRESSING & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES ARMOURED CABLE - UNDRESSED & REMOVAL. - DRESSING OF CABLE IS INCLUDED. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING	15.000	M	10.78	161.70

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
80	Service Code : INREMGLA1A0023 Service Description : CAB. GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARM.CABLE GLD (S-D)/F/L/T(ONE SIDE) & CABLE TERMINATION WITH LUGGING & FERRULING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INCLUDES ARMoured CABLE GLANDING (SINGLE/DOUBLE COMPRESSION), FERRULING, LUGGING & TERMINATION. - INCLUDING SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - DOING FERRULING IS IN CONTRACTORS SCOPE & FERRULS ARE IN AIL SCOPE. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	11.000	NOS	54.95	604.45

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
90	Service Code : INREMGLA1A0064 Service Description : REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - REMOVE ARM.CABLE GLD(S-D)/F/L/T(1-SIDE) - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INSTRUMENTATION ARMOURED CABLE TERMINATION & GLAND REMOVAL (SING/DOUBLE COMPRESSION) - INCLUDINGREMOVAL OF SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	8.000	NOS	23.00	184.00
100	Service Code : ININTSTRIA0002 Service Description : INSTAL. OF EARTH. STRIP 35-50 MMX 5-6 MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK - - INSTAL. OF EARTH. STRIP : INCLUDES DRILLING (HOLE MAKING) AND STRIP JOINT BY NUT-BOLTS. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	6.000	M	56.00	336.00

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
110	Service Code : ININTFAN1A0001 Service Description : INSTAL.& CONN. OF CEILING/WALL MOUNT FAN PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK - - INSTALLATION OF ELECTRICAL DEVICES / COMPONENTS / ACCESSORIES - INCLUDES DRILLING / WELDING FOR INSTALLATIONS. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	1.000	NOS	165.77	165.77
120	Service Code : INREMT/L1A0004 Service Description : REMOVE T/L FIT.1X40W / 2X40W FLP INDUST PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK - - REMOVAL OF ELECTRICAL DEVICES / COMPONENTS / ACCESSORIES - INCLUDES DRILLING / CUTTING FOR REMOVAL. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	1.000	NOS	151.25	151.25

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
130	Service Code : ININTCBT1A0001 Service Description : INSTL CAB TRAY GI/FRP(PER/LAD)25-75MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : FAB.& INSTAL. OF CABLE TRAY / SUPPORTS (PERFORATED / LADDER) - GI / FRP / MS - WHICHEVER IS APPLICABLE. SCOPE OF WORK: - INSTALLATION OF PREFABRICATED CABLE TRAYS AND ALIGN/JOINTING/GRINDING ETC. - INCLUDES DRILLING HOLES ON FRAMES / TRAYS - IN CONTRACTOR'S SCOPE - INCLUDES SHIFTING OF MATERIAL - STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE	1.000	M	51.98	51.98
140	Service Code : ININTANC1A0001 Service Description : DRIL.& INST ANCHOR FAST.4-10 X 100/150MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : INSTALLATION OF ANCHOR FASTNER SCOPE OF WORK: - INCLUDES DRILLING & INSTALLATION OF ANCHOR FASTNERS - INCLUDES SHIFTING OF MATERIAL - STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - IF APPLICABLE - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE	16.000	NOS	41.20	659.20

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No. : 11/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
150	Service Code : ININTANC1A0002 Service Description : DRILL & INST ANCHOR FAST.12-30 X100/150MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : INSTALLATION OF ANCHOR FASTNER SCOPE OF WORK: - INCLUDES DRILLING & INSTALLATION OF ANCHOR FASTNERS - INCLUDES SHIFTING OF MATERIAL STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - IF APPLICABLE - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE	21.000	NOS	47.08	988.68
160	Service Code : ESFABCLPIAD002 Service Description : FAB.& INST. MS TRAY C-CLAMP 300-600MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 FAB.& INST. MS TRAY C-CLAMP 300-600MM FABRICATION MS TRAY C-CLAMP Scaffolding and P&M is in AIL Scope FIM - Free Issue material from AIL	2.000	NOS	242.00	484.00
170	Service Code : MEDISLAC1AD003 Service Description : REM. CAB TRAY GI/FRP(PER/LAD)225-400MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: REM. CAB TRAY GI/FRP(PER/LAD)225-400MM Coating / Lining Works Dismantling Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: M denotes to Meter	3.000	M	45.00	135.00



SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
180	Service Code : MEDISEQPIAD352 Service Description : REMOVAL GI TRAY L/Z/T SUP.100-200MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: REMOVAL GI TRAY L/Z/T SUP.100-200MM Equipment Dismantling Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	1.000	NOS	88.28	88.28
190	Service Code : MPELE0000N0005 Service Description : ELECTRICIAN SUPPLY PER DAY PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 ELECTRICIAN SUPPLY PER DAY	4.000	DAY	750.00	3,000.00
200	Service Code : MEFINEQPIAD139 Service Description : FITTER / WELDER PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: FITTER / WELDER Equipment Fitting / Installation Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: D denotes to Days	2.000	DAY	700.00	1,400.00
210	Service Code : RSMIS0000CM003 Service Description : MAN POWER SUPPLY - HELPER PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 MAN POWER SUPPLY - HELPER; ; #Service Scope : Not Applicable; #Material Scope : Partial material in BP's scope-refer DOR; #UOM : D	5.000	D	600.00	3,000.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No : 13/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
220	Service Code : MESFTEQPIAD147 Service Description : SHIFTING OF INST. FROM PLANT TO STORE/WS PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFTING OF INST. FROM PLANT TO STORE/WS Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	1.000	NOS	66.55	66.55
230	Service Code : MESFTEQPIAD131 Service Description : SHIFT. BIG CABLE DRUM STORE - W.S. PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFT. BIG CABLE DRUM STORE - W.S. Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	1.000	NOS	442.75	442.75
240	Service Code : MERGNINSIAD003 Service Description : LOAD/UNLD. CABLE TRAY / STEEL- 1 T WEIGHT PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT QA/AC Rigging Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: T denotes to "TON, Metric (1000 kg)"	9.000	T	600.00	5,400.00



Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
250	Service Code : INLYDCBF1A0006 Service Description : CABLE LAYING FLEX. 3-4C X 1.0/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - FLEXIBLE CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - INCLUDES LAYING & DRESSING OF FLEXIBLE CABLE - TIE UP AT EACH 300 MM BY USING CABLE / TIE. - THIS DOSEN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	20.000	M	6.00	120.00
260	Service Code : INLYDCBF1A0013 Service Description : CABLE LAYING FLEX.EART.1C X 1.5-6.0 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - FLEXIBLE CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - INCLUDES LAYING & DRESSING OF FLEXIBLE CABLE - TIE UP AT EACH 300 MM BY USING CABLE / TIE. - THIS DOSEN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	11.000	M	7.00	77.00

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
270	Service Code : INRMDCBF1A0014 Service Description : CABLE REMOVE FLEX.EART.IC X 1.5-6.0 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP -FLEXIBLE CABLE UNDRESSED & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - REMOVAL OF FLEXIBLE CABLE - DRESSING OF CABLES IS INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING.	4.000	M	3.38	13.52
280	Service Code : INLYDCBA1A0024 Service Description : CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES LAYING & DRESSING OF ARMOURED CABLE - TIE UP AT EVERY 300 MM BY USING WIRE / TIE. - THIS DOSEN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	27.000	M	20.02	540.54

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
290	Service Code : INLYDCBA1A0042 Service Description : OLD CABLE DRESSING ONLY-RUN. MT. TRAY PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK: - OLD CABLE DRESSING IS APPLICABLE FOR DRESSING OF OLD CABLES DUE TO HOUSEKEEPING OR UNSAFE CONDITION JOBS. - OLD CABLE DRESSING MEANS: DRESSING OF EXISTING MULTIPLE CABLES UPTO 10 NOS. IN A TRAY MEASUREMENT WITH RUNNING METER LENGTH OF TH - IF CABLES ARE MORE THAN 10 NOS. THEN WILL BE IN MULTIPLICATION OF 10 EQUALS TO 1, IF CABLES ARE 15 THE RATE WILL BE DOUBLE, IF CAB - IF CABLE OD IS 1-30 MM (ALL INSTRUMENTATION CABLES - UPTO 48 CORE & 24 PAIR & POWER CABLES UP TO 1 TO 4 CORE 16 SQMM) THEN RATE IS - IF CABLE OD IS 31 MM AND ABOVE (ALL INSTRUMENTATION CABLES - ABOVE 48 CORE or 24 PAIR & POWER CABLES 1- 4 CORE ABOVE 16 SQMM THEN - MATERIAL FOR REDRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	29.000	M	45.00	1,305.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No. : 17/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
300	Service Code : INRMDCBA1A0024 Service Description : CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE UNDRESSING & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES ARMOURED CABLE UNDRESSED & REMOVAL. - DRESSING OF CABLE IS INCLUDED. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING	22.000	M	10.78	237.16
310	Service Code : INLYDCON1A0005 Service Description : CONDUIT LAYING FOR CABLE (U/O GND)-1.5" PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - CONDUIT LAYING FOR CABLE (UND/OVER GRD) SCOPE OF WORK - - PVC/FLEXIBLE/METALLIC CONDUIT LAYING WITH PROPER SUPPORT, SADDLLING, DRILLING ON WALL & JOINTING FOR CABLE LAYING. - UNDER OR OVER - IN CASE OF UNDER GROUND-ESCAVATION AND REFILLING OF SOIL/SAND IS NOT INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	10.000	M	13.07	130.70



AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No. : 18/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
320	Service Code : INREMGLA1A0023 Service Description : CAB. GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARM.CABLE GLD (S-D)/F/L/T(ONE SIDE) & CABLE TERMINATION WITH LUGGING & FERRULING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INCLUDES ARMOURED CABLE GLANDING (SINGLE/DOUBLE COMPRESSION), FERRULING, LUGGING & TERMINATION. - INCLUDING SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - DOING FERRULING IS IN CONTRACTORS SCOPE & FERRULS ARE IN AIL SCOPE. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	5.000	NOS	54.95	274.75

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No. : 19/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
330	Service Code : INREMGLA1A0064 Service Description : REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - REMOVE ARM.CABLE GLD(S-D)/F/L/T(1-SIDE) - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INSTRUMENTATION ARMoured CABLE TERMINATION & GLAND REMOVAL (SING/DOUBLE COMPRESSION) - INCLUDINGREMOVAL OF SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	3.000	NOS	23.00	69.00
340	Service Code : ININTT/L1A0004 Service Description : INSTAL. T/L FIT.1X40W / 2X40W FLP INDUST PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK - - INSTALLATION OF ELECTRICAL DEVICES / COMPONENTS / ACCESSORIES - INCLUDES DRILLING / WELDING FOR INSTALLATIONS. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	3.000	NOS	302.50	907.50



SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
350	Service Code : INREMT/L1A0004 Service Description : REMOVE T/L FIT.1X40W / 2X40W FLP INDUST PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 SCOPE OF WORK - - REMOVAL OF ELECTRICAL DEVICES / COMPONENTS / ACCESSORIES - INCLUDES DRILLING / CUTTING FOR REMOVAL. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	3.000	NOS	151.25	453.75
360	Service Code : ININTCBT1A0001 Service Description : INSTL CAB TRAY GI/FRP(PER/LAD)25-75MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : FAB.& INSTAL. OF CABLE TRAY / SUPPORTS (PERFORATED / LADDER) - GI / FRP / MS - WHICHEVER IS APPLICABLE. SCOPE OF WORK: - INSTALLATION OF PREFABRICATED CABLE TRAYS AND ALIGN/JOINTING/GRINDING ETC. - INCLUDES DRILLING HOLES ON FRAMES / TRAYS - IN CONTRACTOR'S SCOPE - INCLUDES SHIFTING OF MATERIAL STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE	2.000	M	51.98	103.96

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
370	Service Code : MEDISEQPIAD360 Service Description : REMOVAL MS TRAY L/Z/T SUP.400-600MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: REMOVAL MS TRAY L/Z/T SUP.400-600MM Equipment Dismantling Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	1.000	NOS	102.99	102.99
380	Service Code : MPELE0000N0005 Service Description : ELECTRICIAN SUPPLY PER DAY PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 ELECTRICIAN SUPPLY PER DAY	10.000	DAY	750.00	7,500.00
390	Service Code : RSMIS0000CM003 Service Description : MAN POWER SUPPLY - HELPER PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 MAN POWER SUPPLY - HELPER; ; #Service Scope : Not Applicable; #Material Scope : Partial material in BP's scope-refer DOR; #UOM : D	3.000	D	600.00	1,800.00
400	Service Code : MESFTEQPIAD147 Service Description : SHIFTING OF INST. FROM PLANT TO STORE/WS PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFTING OF INST. FROM PLANT TO STORE/WS Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	12.000	NOS	66.55	798.60

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

Page No. : 22/38

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
410	Service Code : MESFTEQPIAD135 Service Description : SHIFT. INST. CART. BOX 2'X3' STORE TO WS PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFT. INST. CART. BOX 2'X3' STORE TO WS Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	10.000	NOS	181.50	1,815.00
420	Service Code : MESFTEQPIAD134 Service Description : SHIFT. CV-FT STORE / WS TO PLANT UPTO 2" PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFT. CV-FT STORE / WS TO PLANT UPTO 2" Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	1.000	NOS	201.28	201.28
430	Service Code : MERGNINSIAD003 Service Description : LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT QA/AC Rigging Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: T denotes to "TON, Metric (1000 kg)"	5.000	T	600.00	3,000.00



AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
440	Service Code : ESLUNMTR1A0001 Service Description : SHIFT. / LOAD/UNLOAD OF MOTOR UPTO 15 HP PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - SERVICES FOR SHIFTING & LOADING / UNLOADING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - SHIFTING OF MATERIAL FROM ONE PLACE TO ANOTHER PLACE AND INCLUDED FOR MULTIPLE FLOORS. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE APPLICABLE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - UNLOADING INCLUDES - UNLOADING FROM TRUCK/TEMPO AND PLACING TO W/S OR STORES OR PLANT OR AT DESIGNATED PLACE. - LOADING INCLUDES -OR LOADING INTO TRUCK/TEMPO INCLUDES TAKING FROM STORES OR W/S OR PLANT OR DESIGNATED PLACE.	1.000	NOS	203.00	203.00
450	Service Code : INLYDCBF1A0006 Service Description : CABLE LAYING FLEX. 3-4C X 1.0/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - FLEXIBLE CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - INCLUDES LAYING & DRESSING OF FLEXIBLE CABLE - TIE UP AT EACH 300 MM BY USING CABLE / TIE. - THIS DOESN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	31.000	M	6.00	186.00

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
460	Service Code : INLYDCBF1A0013 Service Description : CABLE LAYING FLEX.EART.IC X 1.5-6.0 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - FLEXIBLE CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - INCLUDES LAYING & DRESSING OF FLEXIBLE CABLE - TIE UP AT EACH 300 MM BY USING CABLE / TIE. - THIS DOESN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	20.000	M	7.00	140.00
470	Service Code : INRMDCBF1A0007 Service Description : CABLE REMOVE FLEX. 3-4C X 1.0/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP -FLEXIBLE CABLE UNDRESSED & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - REMOVAL OF FLEXIBLE CABLE - DRESSING OF CABLES IS INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING.	20.000	M	3.00	60.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
480	Service Code : INLYDCBA1A0024 Service Description : CABLE LAYING ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE LAYING & DRESSING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES LAYING & DRESSING OF ARMOURED CABLE - TIE UP AT EVERY 300 MM BY USING WIRE / TIE. - THIS DOSEN'T INCLUDES GLANDING & TERMINATION. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	56.000	M	20.02	1,121.12
490	Service Code : INRMDCBA1A0023 Service Description : CABLE REMOVE ARM. TELE. 50-100P PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMOURED CABLE UNDRESSING & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES ARMOURED CABLE UNDRESSED & REMOVAL. - DRESSING OF CABLE IS INCLUDED. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING	35.000	M	16.17	565.95

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
500	Service Code : INRMDCBA1A0024 Service Description : CABLE REMOVE ARM. 3-4C X 1/1.5/2.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARMoured CABLE UNDRESSING & REMOVAL - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK- - INCLUDES ARMoured CABLE UNDRESSED & REMOVAL. - DRESSING OF CABLE IS INCLUDED. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - MATERIAL FOR DRESSING IS IN AIL SCOPE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - OLD CABLE REDRESSING IS ADDITIONAL AGAINST SEPARATE SERVICE CODE. - REDRESSING IS NOT APPLICABLE FOR THE CABLES LAYED INTO PIPE OR DUCT / CASING	63.000	M	10.78	679.14
510	Service Code : INLYDCON1A0005 Service Description : CONDUIT LAYING FOR CABLE (U/O GND)-1.5" PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - CONDUIT LAYING FOR CABLE (UND/OVER GRD) SCOPE OF WORK - - PVC/FLEXIBLE/METALLIC CONDUIT LAYING WITH PROPER SUPPORT, SADDLING, DRILLING ON WALL & JOINTING FOR CABLE LAYING. - UNDER OR OVER - IN CASE OF UNDER GROUND-ESCAVATION AND REFILLING OF SOIL/SAND IS NOT INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	18.000	M	13.07	235.26

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
520	Service Code : INREMCON1A0004 Service Description : CONDUIT REMOVE FOR CABLE (U/O GND)-1.5" PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - CONDUIT REMOVAL OF CABLE (UND/OVER GRD) SCOPE OF WORK - - PVC/FLEXIBLE/METALLIC CONDUIT REMOVAL WITH JOINTS, SADDLES - UNDER OR OVER GROUND /INDOOR/INTO CABLE TRAYS. - IN CASE OF UNDER GROUND-ESCAVATION AND REFILLING OF SOIL/SAND IS NOT INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	10.000	M	6.53	65.30
530	Service Code : INREMGLA1A0023 Service Description : CAB. GLD/F/L/T ARM. 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - ARM.CABLE GLD (S-D)/F/L/T(ONE SIDE) & CABLE TERMINATION WITH LUGGING & FERRULING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INCLUDES ARMOURED CABLE GLANDING (SINGLE/DOUBLE COMPRESSION), FERRULING, LUGGING & TERMINATION. - INCLUDING SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - DOING FERRULING IS IN CONTRACTORS SCOPE & FERRULS ARE IN AIL SCOPE. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	16.000	NOS	54.95	879.20

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
540	Service Code : INREMGLA1A0064 Service Description : REMOVE GLD & TER ARM 3-4C X 1/1.5 SQMM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - REMOVE ARM.CABLE GLD(S-D)/F/L/T(1-SIDE) - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK - - INSTRUMENTATION ARMOURED CABLE TERMINATION & GLAND REMOVAL (SING/DOUBLE COMPRESSION) - INCLUDING REMOVAL OF SHIELD/SCREEN TERMINATION. - THIS INCLUDES ONE SIDE OF CABLE. - INCLUDES DRESSING INSIDE PANEL. - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE REQUIRED - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	12.000	NOS	23.00	276.00
550	Service Code : ININTCBT1A0001 Service Description : INSTL CAB TRAY GI/FRP(PER/LAD)25-75MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : FAB.& INSTAL. OF CABLE TRAY / SUPPORTS (PERFORATED / LADDER) - GI / FRP / MS - WHICHEVER IS APPLICABLE. SCOPE OF WORK: - INSTALLATION OF PREFABRICATED CABLE TRAYS AND ALIGN/JOINTING/GRINDING ETC. - INCLUDES DRILLING HOLES ON FRAMES / TRAYS - IN CONTRACTOR'S SCOPE - INCLUDES SHIFTING OF MATERIAL STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE	73.000	M	51.98	3,794.54

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
560	Service Code : INFABSUP1A0003 Service Description : FAB&INST.GI/FRP TRAY L/Z/T SUP.225-300MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : FAB.& INSTAL. OF SUPPORTS (L/Z/T/S/CLITS/INSERT PLATES), PIPE SUPPORTS, CLAMPS, FRAMES - GI / FRP / MS - WHICHEVER IS APPLIC SCOPE OF WORK : - INCLUDES FABRICATION & INSTALLATION OF MS / GI / FRP SUPPORTS OR CLAMPS OR ANGLE/CHANNEL FRAMES AND ALIGN/JOINTING/GRINDING ETC. - INCLUDES DRILLING / HOLES MAKING ON SUPPORTS / CLAMPS / FRAMES - IN CONTRACTOR'S SCOPE - INCLUDES SHIFTING OF MATERIAL STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	1.000	NOS	196.00	196.00
570	Service Code : INFABSUP1A0004 Service Description : FAB&INST.GI/FRP TRAY L/Z/T SUP.350-450MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP : FAB.& INSTAL. OF SUPPORTS (L/Z/T/S/CLITS/INSERT PLATES), PIPE SUPPORTS, CLAMPS, FRAMES - GI / FRP / MS - WHICHEVER IS APPLIC SCOPE OF WORK : - INCLUDES FABRICATION & INSTALLATION OF MS / GI / FRP SUPPORTS OR CLAMPS OR ANGLE/CHANNEL FRAMES AND ALIGN/JOINTING/GRINDING ETC. - INCLUDES DRILLING / HOLES MAKING ON SUPPORTS / CLAMPS / FRAMES - IN CONTRACTOR'S SCOPE - INCLUDES SHIFTING OF MATERIAL STORE/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE.	1.000	NOS	225.00	225.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
580	Service Code : MEDISLACIAD003 Service Description : REM. CAB TRAY GI/FRP(PER/LAD)225-400MM PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: REM. CAB TRAY GI/FRP(PER/LAD)225-400MM Coating / Lining Works Dismantling Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: M denotes to Meter	4.600	M	45.00	207.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
590	Service Code : ININTPBS1A0002 Service Description : INSTALLATION OF PB STATION-FLP PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - INSTRUMENTATION / ELECTRICAL - SWITCH GEAR INSTALLATION SCOPE OF WORK - - INSTALLATION OF SWITCH GEARS IN EXISTING CUTOUTS. - TERMINATION (IN/OUT) IS INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE APPLICABLE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. NEW INSTALLATION MEANS - REQUIRES TWO SERVICES : INSTALLATIONS OF DEVICE / INSTRUMENT + GLANDING & TERMINATION. REPLACEMENT MEANS - REQUIRES FOUR SERVICES : REMOVAL OF GLAND & TERMINATION + REMOVAL OF DEVICE / INSTRUMENT + INSTALLATIONS OF DEV REPAIRS MEANS - REQUIRES FOUR SERVICES : REMOVAL OF GLAND & TERMINATION + REMOVAL OF DEVICE / INSTRUMENT + REPAIRS (SERVICE OF INSTA	1.000	NOS	190.00	190.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
600	Service Code : INREMPBS1A0004 Service Description : REMOVAL OF PB STATION-FLP PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - INSTRUMENTATION / ELECTRICAL-SWITCH GEAR REMOVAL SCOPE OF WORK - - REMOVAL OF SWITCH GEARS - TERMINATION (IN/OUT) IS INCLUDED - INCLUDES SHIFTING OF MATERIAL-STORES/WORKPLACE - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE APPLICABLE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. REMOVAL MEANS - REQUIRES TWO SERVICES : REMOVAL OF GLAND & TERMINATION + REMOVAL OF DEVICE / INSTRUMENT	2.000	NOS	78.65	157.30
610	Service Code : MPELE0000N0005 Service Description : ELECTRICIAN SUPPLY PER DAY PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 ELECTRICIAN SUPPLY PER DAY	5.000	DAY	750.00	3,750.00
620	Service Code : RSMIS0000CM003 Service Description : MAN POWER SUPPLY - HELPER PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 MAN POWER SUPPLY - HELPER; ; #Service Scope : Not Applicable; #Material Scope : Partial material in BP's scope-refer DOR; #UOM : D	4.000	D	600.00	2,400.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
630	Service Code : MESFTEQPIAD135 Service Description : SHIFT. INST. CART. BOX 2'X3' STORE TO WS PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: SHIFT. INST. CART. BOX 2'X3' STORE TO WS Equipment Lifting Shifting Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: NOS denotes to Numbers	11.000	NOS	181.50	1,996.50
640	Service Code : MERGNINSIAD003 Service Description : LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 Description: LOAD/UNLD CABLE TRAY / STEEL- 1 T WEIGHT QA/AC Rigging Service Scope: Scaffolding and P&M is in AIL Scope Material Scope: FIM - Free Issue material from AIL UOM: T denotes to "TON, Metric (1000 kg)"	10.000	T	600.00	6,000.00

AARTI INDUSTRIES LTD-VAPI (Plant: APPLE UNIT)

SERVICE WORK ORDER - 3190012304

Item No.	Item Description	Quantity	Unit	Rate	Total Amount (INR)
650	Service Code : ESLUNMTR1A0001 Service Description : SHIFT. / LOAD/UNLOAD OF MOTOR UPTO 15 HP PR no : 25008613-10 GST : 18.00 % Account assignment no : 4001859 20 GROUP - SERVICES FOR SHIFTING & LOADING / UNLOADING - INSTRUMENTATION / ELECTRICAL SCOPE OF WORK: - SHIFTING OF MATERIAL FROM ONE PLACE TO ANOTHER PLACE AND INCLUDED FOR MULTIPLE FLOORS. - SCAFFOLDING, P&M (FARANA / HYDRA / CRANE) IS IN AIL SCOPE - WHERE APPLICABLE. - TOOLS & TACKLES WILL BE IN CONTRACTOR'S SCOPE. - UNLOADING INCLUDES - UNLOADING FROM TRUCK/TEMPO AND PLACING TO W/S OR STORES OR PLANT OR AT DESIGNATED PLACE. - LOADING INCLUDES -OR LOADING INTO TRUCK/TEMPO INCLUDES TAKING FROM STORES OR W/S OR PLANT OR DESIGNATED PLACE.	1.000	NOS	203.00	203.00
				Total (Excl. tax)	61,906.03
				CGST Tax	5571.54
				SGST Tax	5571.54
				Total (inc. tax)	73,049.11